

## 1. SCOPE

- a) These Specifications cover all operations necessary for and pertaining to:
  - i) Construction of new cast-in-place concrete pile foundations for traffic signal and pedestrian corridor structures;
  - ii) Construction of concrete pile extensions at existing locations;
  - iii) Repair of concrete foundations at existing locations; and,
  - iv) Construction of Controller Base foundations.
- b) The Work shall be done in accordance with these Specifications and as shown on the Drawings. The Work by the Contractor shall include the furnishing of all superintendence, overhead, labour, materials, equipment, tools, supplies, and all things necessary for and incidental to the satisfactory performance and completion of all Works as hereinafter specified.

## 2. MATERIALS

### 1.1 General

- a) Notwithstanding and in addition to Specification No. 1018M "Specifications for Placing Cast-in-Place Concrete Piles", and Specification No. 1030(I) "Specifications for Reinforced Cast-in-Place Concrete", the following shall apply.
- b) The Contractor shall be responsible for the supply, safe storage, and handling of all materials set forth in this Specification.
- c) All materials shall be handled and stored in a careful and workmanlike manner, to the satisfaction of the Engineer. Storage of materials shall be in accordance with CSA Standard A23.1 (latest edition).

### 1.2 Testing and Approval

- a) All materials supplied under this Specification shall be subject to inspection and testing by the Engineer. There shall be no charge to the Department for any materials taken by the Engineer for testing purposes.
  - b) All materials shall be approved by the Engineer before any construction is undertaken. If, in the opinion of the Engineer, such materials in whole or in part, do not conform to the Specifications detailed herein or are found to be defective in manufacture or have become damaged in transit, storage, or handling operations, then such materials shall be rejected by the Engineer and replaced by the Contractor at his own expense.
-

### 1.3 Anchor Bolt Assembly

- a) Each anchor bolt assembly consists of the anchor bolt, four (4) Heavy Hex Nuts, four (4) Hardened Washers and one (1) Half-Nut according to the sizes shown on the Drawings.
- b) Anchor bolts shall be in accordance with ASTM F1554 Grade 55 (380 MPa).
- c) Heavy Hex Nuts shall be in accordance with ASTM A194 Grade 2H.
- d) Hardened Washers shall be in accordance with ASTM F436.
- e) The anchor bolt assembly shall be hot-dip galvanized full length in accordance with ASTM A123-17 (latest edition) with net retention of 610 g/m<sup>2</sup>.
- f) The anchor bolt assemblies will be incidental to the construction of concrete pile foundation Work and no separate payment will be made.

### 1.4 Anchor Bolt Setting Templates

- a) Anchor bolt setting templates (top and bottom) shall be minimum 10 mm thick and in accordance with CSA G40.21, Grade 350W.
- b) The permanent bottom setting plate shall be hot-dip galvanized in accordance with ASTM A123-17 (latest edition) with net retention of 610 g/m<sup>2</sup>.
- c) The anchor bolt setting templates will be incidental to the construction of concrete pile foundation Work and no separate payment will be made.

### 1.5 Anchor Bolt Extensions and Accessories

- a) Anchor bolt couplings shall be Williams C2T Stop-type Coupling matching the size of existing anchor bolts.
  - b) Anchor bolt extension rod shall be ASTM F1554 Grade 55 (380 MPa).
  - c) Anchor bolt extensions and accessories plate shall be hot-dip galvanized in accordance with ASTM A123-17 (latest edition) with net retention of 610 g/m<sup>2</sup>.
  - d) The anchor bolt extensions and accessories will be incidental to the construction of concrete pile extension Work and no separate payment will be made.
-

Specification For: Concrete Foundations for Traffic Signal and Pedestrian Corridor Structures

#### 1.6 Concrete

- a) Concrete shall conform to the notes on the Drawing and Specification No. 1030 (I), "Specifications for Reinforced Cast-in-Place Concrete" and shall be the type therein described for cast-in-place piles.

#### 1.7 Reinforcing Steel

- a) Reinforcing steel shall be deemed to include all reinforcing bars, tie-bars, and dowels.
- b) All reinforcing steel shall conform to the requirements of CSA G30.18, Grade 400W, Billet-Steel Bars for Concrete Reinforcement. All reinforcing steel shall be new deformed billet steel bars.

#### 1.8 Electrical Raceways

- a) Electrical raceways shall be 53 mm dia. plastic pipe and 27 mm dia. plastic pipe and shall include all incidentals, including watertight splice connections, where applicable.

### 3. SUBMITTALS

- a) Where the applicable Workplace Safety and Health Regulations require rigging and/or erection plans to be designed or otherwise certified by a Registered Professional Engineer, the Contractor shall submit the applicable documents and certifications to the Department.
- b) The Contractor shall submit Traffic Management Plans (TMP) to the Department for review at least ten (10) working days prior to carrying out the Work.

### 4. SITE CONDITIONS

#### 4.1 Site Visit

- a) Bidders are responsible for visiting the site and carrying out a visual inspection of the site(s) as well as determining and evaluating all existing site conditions, including traffic conditions, prior to the tender closing date.
  - b) Failure to undertake a site visit and carry out an inspection shall not relieve bidders of the responsibility to ascertain the full extent of the Work and to perform all Work in accordance with the Contract.
  - c) Claims for additional costs will not be entertained with respect to conditions and existing installations which would have been ascertained by an inspection of the site(s) prior to tender closing date.
-

#### 4.2 Cooperation with Others

- a) Other parties such as Contractors, utility companies, and/or Manitoba Infrastructure personnel may be working on or adjacent to the Project Site(s) during the course of the Work. The Contractor shall cooperate fully with others with respect to the scheduling, coordinating, accessing and conducting of their respective operations, as well as the Contractor's operations.
- b) No additional compensation will be made to the Contractor for his cooperation with others who may be undertaking Work at or near the Project Site(s) during the course of the Contract as this is considered to be incidental to the Contract.

#### 5. EQUIPMENT

- a) All equipment shall be of a type approved by the Engineer and shall be kept in good working order.
- b) The Contractor shall provide all the required equipment for the projects of this contract. Failure to provide the required equipment for any of the project sites of this contract will result in Work stoppage for the Contractor until all the required equipment is at the project site.
  - i) Auger / Coring equipment.
  - ii) Sleeving equipment.
  - iii) Trenching equipment to provide a single trench (Width – minimum 100 mm and up to a maximum of 300 mm) x (Depth – minimum 1000 mm).
  - iv) Horizontal directional drill only, shall be required for electrical conduit installations.
  - v) Hydro vac equipment.
  - vi) Backhoe and operator.
  - vii) Compressor, hoses, jackhammer, drill complete with bits capable of installing 38 mm electrical conduit.
  - viii) Plate Compactor or Jumping Jack Compactor shall be required equipment on all project sites of the Contract.
  - ix) Portable water pump and hose shall be required equipment on site for all the concrete pile foundation installations of the contract in the event that water is encountered.
  - x) Portable electric concrete vibrator shall be required equipment on site for all concrete Work of the Contract – minimum length required 2 meters.
  - xi) Saw cutting equipment for vehicle detector loop installation.
  - xii) All required construction signs and stands for the Contract – condition of signs and stands shall meet Department Specifications.
  - xiii) Portable electric generator to power electrical equipment and tools.

## 6. CONSTRUCTION METHODS

### 6.1 Standard Drawings

Standard Drawings for Concrete Pile Foundations forming part of this Specification include the drawings listed in Table 1.

Table 1: List of Standard Drawings – Concrete Pile Foundations

Drawing No.	Description	Part No.
F1	Light Series Foundation: a) 610 mm Dia. Pile b) 610 mm Dia. Pile for Breakaway Base	F-L F-L(BR)
F2	Medium Series Foundation – 762 mm Dia. Pile	F-M
F3	Heavy Series Foundation – 915 mm Dia. Pile	F-H
F4	Extra Heavy Series Foundation – 1220 mm Dia. Pile	F-EH
A1	Anchor Bolts: a) 32 mm (1 1/4") Dia. Anchor Bolt b) 38 mm (1 1/2") Dia. Anchor Bolt c) 51 mm (2") Dia. Anchor Bolt	AB1 AB2 AB3

## 7. LAYOUT OF THE WORK

- a) The Department will lay out the center of pile foundations and the elevation to the top of concrete. The Contractor shall be responsible for providing offset markers or elevations prior to the start of construction.
- b) The Contractor shall verify all layout is in accordance with the Drawings prior to the start of construction work.

### 7.1 General

- a) Notwithstanding and in addition to Specification No. 1018M "Specifications for Placing Cast-in-Place Concrete Piles", and Specification No. 1030(I) "Specifications for Reinforced Cast-in-Place Concrete", the Specifications herein shall apply.

### 7.2 Commencing Work

- a) The Contractor shall notify the Project Supervisor at least five (5) working days prior to commencing Work at any location.

### 7.3 Scheduling of Work

- a) Construction operations and sequence shall be subject to the approval of the Engineer.
- b) Where services of other Contractors or Agencies are required, in connection with the satisfactory execution of the Work, the Contractor shall notify all parties involved.
- c) No extra compensation will be paid to the Contractor for any inconvenience or extra expense incurred as a result of delay by others.

### 7.4 Traffic Control

- a) The Contractor shall provide traffic control in accordance with the latest edition of the Department's "Specifications for Traffic Control" – Level II Modified, gateway assemblies not required.
- b) Traffic Control will be considered incidental to the Work of this Specification.

### 7.5 Location and Alignment of Foundations

- a) Foundations shall be placed in the positions shown on the Drawings and as directed by the Engineer in the field.
- b) The deviation of the axis of any finished pile shall not differ by more than 1% from the vertical.

### 7.6 Buried Utilities

- a) The Contractor shall exercise extreme caution when constructing the pile foundations in the vicinity of existing buried utilities. The Contractor shall be responsible for obtaining the exact location of the buried utilities from the appropriate Utility Authority prior to installing the foundations. Hydro vac equipment shall be used for exposure of all underground utilities, Department Traffic Signal underground equipment, and new concrete pile foundation installations near any underground utilities, and Department Traffic Signal underground equipment.
  - b) The proposed locations of the concrete foundations may be changed by the Engineer if they interfere with the buried utilities.
  - c) The Contractor shall be responsible for all costs that may be incurred for repair/rectification of any damage caused to the existing buried utilities as a result of the Contractor's operations in constructing cast-in-place concrete foundations, as determined by the Engineer.
  - d) The Contractor shall be responsible for all underground utility clearances, and the Department underground traffic signal plant clearances for the various Contract projects. At the request of the Engineer the Contractor shall make available all the utility clearance documents for each Contract project. The Contractor shall expose all underground utilities and the Department underground
-

Specification For: Concrete Foundations for Traffic Signal and Pedestrian Corridor Structures

traffic signal plant with only hydro vac equipment before any underground electrical conduits are installed. The Engineer on site shall inspect the exposed underground utility before the installation of any underground electrical conduits. Sand shall be used to backfill the excavated area of the exposed underground utility, or exposed underground traffic signal plant.

- e) Exploration for determining the location of underground utilities will be considered incidental to the Work of this Specification.

#### 7.7 Restoration of Adjacent Property

- a) The restoration of existing concrete sidewalks/medians and curbs, as well as boulevard median, paving stone, or sodding, required as shown on the Drawings, will be incidental to the construction of cast-in-place concrete foundations, and no separate payment will be made.
- b) Sidewalk or median concrete paving shall be saw cut at least 300 mm all around from the edge of pile and restored flush with adjacent surface level after the foundation Work has been completed. An isolation joint shall be provided in accordance with Plan No. MISC-3.
- c) During the course of the Work, the Contractor shall keep the workplace in a neat and tidy condition, satisfactory to the Engineer. The Contractor shall, upon the completion of the Work, remove all temporary structures and clean away all rubbish, surplus, and waste material remaining on or about the workplace, satisfactory to the Engineer.
- d) If these requirements are not met, the Engineer shall give notice requiring the Contractor to remedy the situation. Should the Contractor fail to remedy the situation within 48-hours of receipt of this notice, the Engineer shall cause the situation to be remedied at the expense of the Contractor.

### 8. CONSTRUCTION METHODS FOR NEW CONCRETE FOUNDATIONS

#### 8.1 General

- a) Notwithstanding and in addition to Specification No. 1018M "Specifications for Placing Cast-in-Place Concrete Piles", and Specification No. 1030(I) "Specifications for Reinforced Cast-in-Place Concrete", the methods described in this section shall be applicable to the construction of new cast-in-place concrete pile foundations;

#### 8.2 Forms

- a) The top 610 mm of the concrete pile foundations shall be formed with tubular forms (Sonotube).
  - b) A minimum of 75 mm of clear cover shall be provided to all embedded reinforcing steel.
-

Specification For: Concrete Foundations for Traffic Signal and Pedestrian Corridor Structures

- c) The forms shall be sufficiently rigid to prevent lateral or vertical distortions from the loading environment to which they shall be subjected. Forms shall be set to the design grades, lines, and dimensions, as shown on the Drawings.

### 8.3 Installing Anchor Bolts

- a) The anchor bolts shall be aligned with the steel concrete pile foundation template matching the bolt holes in the structure base plate. The traffic signal arm alignment will be determined by the Engineer on site.
- b) Prior to placement of concrete, the top setting template shall be oiled (both inside and out) for ease of removal and cleaning. Extreme care shall be used in this operation.
- c) The bottom setting template shall be held in place by the top and bottom nuts as shown on the Drawings.
- d) Placement of anchor bolts without the top and bottom steel templates shall not be permitted.
- e) The anchor bolts shall not be tied or otherwise in contact with the reinforcing steel.

### 8.4 Installation of Electrical Raceways in Concrete Pile Foundation

- a) The supply and installation of electrical raceways shall be considered incidental to the Work of this Specification.
- b) The installation of electrical raceways into the traffic signal concrete pile foundation shall be installed by licensed electricians. Four (4) electrical raceways consisting of 3 - 5 mm dia. and 1 - 27 mm dia. plastic pipes shall be installed in each concrete pile foundation as shown on the Drawings. The electrical conduits shall enter 900 mm minimum below ground level and shall protrude through the centre of the concrete pile foundation. The two electrical conduits considered as spares shall be plugged with an approved electrical conduit plug, or electrical tape at each end and protected to ensure future accessibility.
- c) An additional 13 mm dia. electrical conduit supplied by the Contractor shall be installed by licensed electricians in the centre of each concrete pile foundation as directed by the Engineer. This is not shown on the Drawings.

### 8.5 Installation of Grounding Conductor

- a) The grounding conductor shall be installed by licensed electricians.
  - b) The copper clad ground rod (3.0 m) and ground wire supplied by the Department shall be installed adjacent (within 1.0 m) to each concrete traffic signal concrete pile foundation. The #6 bare copper ground wire shall be connected to the ground rod with a ground rod clamp. The ground
-



Specification For: Concrete Foundations for Traffic Signal and Pedestrian Corridor Structures

wire shall then be installed through the 13 mm conduit to the centre of the traffic signal concrete pile foundation and terminated above the concrete pile foundation in a 1.0 m coil.

- c) The installation of the grounding conductor shall be considered incidental to the Work of this Specification.

#### 8.6 Placing Concrete

- a) Care shall be taken to ensure that anchor bolts are vertically aligned and that anchor bolts and conduits are properly positioned prior to placement of concrete.
- b) The threaded portion of the anchor bolts projecting above the concrete surface shall be taped with a light gauge PVC electrical tape before the concrete is poured, to minimize the fouling of threads splattered by concrete residue.

#### 8.7 Concrete Pile Foundation Template Removal

- a) After the concrete has been placed the Contractor shall determine the length of time required for the safe removal of the concrete foundation template to complete a first class concrete finish on the surface of the concrete pile foundation. The template shall be placed back on the concrete pile foundation after the first class finish has been completed. After the concrete has cured the Contractor shall determine when the template can be safely removed from the concrete foundation. Removal of the template shall be done in a manner to avoid damage to, or spalling of, the concrete.
- b) Any damage (i.e. cracking or chipping of the concrete) to the concrete foundation surface during removal of the foundation template shall be inspected by the Engineer on site. The Engineer on site shall determine the extent of the damage, and decide whether the concrete foundation shall be repaired or replaced. Any repair or replacement of the concrete foundation shall be at the Contractor's own expense.

### 9. CONSTRUCTION METHODS FOR REBUILT FOUNDATIONS

#### 9.1 General

- a) Notwithstanding and in addition to Specification No. 1018M "Specifications for Placing Cast-in-Place Concrete Piles", and Specification No. 1030(I) "Specifications for Reinforced Cast-in-Place Concrete", the following shall apply.
  - b) Concrete foundations to be extended or repaired shall be identified on the contract drawings and shall be marked by the Engineer before Work commences.
  - c) The following rebuild Work related to existing concrete foundations at designated traffic signal structure sites are covered under this Specification.
-

Specification For: Concrete Foundations for Traffic Signal and Pedestrian Corridor Structures

- d) The construction methods described in this section shall be applicable to:
  - i) Construction of concrete pile extensions, and;
  - ii) Repair of existing concrete foundations.
- e) The Contractor shall include the cost of removing and restoring the existing concrete/asphalt sidewalk paving or sodding or soil surface, as required, in the total cost of the respective repairs as no separate payment will be made for this Work.
- f) The Contractor is advised that the removal, temporary storage, reinstallation of the existing traffic signal structures, and related electrical Work will be done by the Department's Traffic Signal crew unless otherwise specified.

## 9.2 Concrete Removal

- a) The grout pad and deteriorated concrete shall be removed from the top of concrete pile foundation down to sound concrete. The amount of concrete removed shall be determined by the Engineer for concrete foundations requiring repairs, and for concrete pile foundations requiring extensions.
- b) The areas requiring removal shall be marked in the field by the Engineer after the Contractor has excavated around the concrete pile foundation.
- c) The perimeter of all concrete identified for removal shall be saw-cut to a minimum depth of 20 mm prior to removal of concrete.

## 9.3 Field-Applied Touch-up Galvanizing

- a) After the concrete has been removed to a depth determined by the Engineer, the Contractor shall field-apply touch-up galvanizing for all exposed anchor bolts and steel reinforcement.
  - b) Surfaces to receive touch-up galvanizing shall be cleaned using a wire brush, a light grinding action, or mild blasting to remove loose scale, rust, paint, grease, dirt, or other contaminants.
  - c) For pure zinc paint on systems, the approved product Zinga shall be applied by either a brush or roller. The Zinga shall be applied in three coats, with each coat having a minimum dry film thickness of 60  $\mu\text{m}$  (2.4 mils). Each coat shall be left to dry for a minimum of one (1) hour before the application of the next coat.
  - d) No additional payment shall be made for this Work as it is considered incidental to the Work of this Specification.
-

#### 9.4 Installation of Dowels, Anchor Bolt Extensions and Conduits

- a) Dowels, which are to be anchored into existing concrete, shall be installed in pre-drilled holes, as shown on the Drawings and grouted in place to the correct grade and alignment. In the event that existing reinforcing steel bars are hit during the drilling operations that hole shall be abandoned and a new hole shall be drilled nearby to the correct depth. All abandoned holes shall be filled with non-shrink non-metallic grout.
- b) All holes shall be thoroughly cleaned prior to installation of dowel bars.
- c) Care shall be taken not to disturb the holes until the grout has set properly. Any dowels, which are found to be loose, shall be removed and reinstalled properly to the satisfaction of the Engineer. After the Engineer has approved the installation of the dowels, the reinforcing steel shall be placed to clearances as shown on the Drawings and shall be positively tied.
- d) Anchor Bolt Extensions shall be installed as shown on the Drawings. The anchor bolt extensions shall be aligned with a template matching the bolt holes in the existing base plate. The setting template shall be held in place by the top and bottom nuts of the anchor bolts.
- e) The size of electrical conduit extensions shall match the existing electrical conduits. The electrical conduit extensions shall be installed by licensed electricians.

#### 9.5 Placing Concrete

- a) The threaded portion of the anchor bolts projecting above the concrete surface shall be taped with a light gauge PVC electrical tape before the concrete is poured, to minimize the fouling of threads splattered by concrete residue.

#### 9.6 Patching of Formed Surfaces

- a) Immediately after forms have been removed, but before any repairing or surface finishing is started, the concrete surface shall be inspected by the Engineer. Any repair of surface finishing started before this inspection may be rejected and required to be removed.
  - b) All formed concrete surfaces shall have bolts, ties, struts, and all other timber or metal parts not specifically required for construction purposes cut back 50 mm from the surface before patching.
  - c) Minor surface defects caused by honeycomb, air pockets greater than 5 mm in diameter, and voids left by strutting, and tie holes shall be repaired by removing the defective concrete to sound concrete, dampening the area to be patched and then applying patching mortar. A slurry grout consisting of water and cement shall be well-brushed onto the area to be patched. When the slurry grout begins to lose the water sheen, the patching mortar shall be applied. It shall be struck-off slightly higher than the surface and left for one hour before final finishing to permit initial shrinkage of the patching mortar and it shall be touched up until it is satisfactory to the
-

Engineer. The patch shall be cured as specified in this Specification, and the final colour shall match the surrounding concrete.

#### 9.7 Installation of Traffic Signal Structures


- a) The traffic signal structures will be installed by the Department's forces unless otherwise specified.

#### 10. CONCRETE TESTING

- a) In addition to Specification 1030 (I) "Specifications for Reinforced Cast-in-Place Concrete", the following shall apply.
- b) All concrete delivered to the project sites for new concrete pile foundations shall be tested. No concrete shall be discharged from the concrete truck until there is a third-party CSA Certified Concrete Technologist on-site to perform concrete testing.
- c) A minimum 26 MPa (75%) compressive strength is required for the safe installation of the traffic signal pole on the new concrete pile foundation.
- d) The Contractor shall be responsible for all the required concrete tests, and all costs incurred for the concrete tests by a CSA Certified Testing Company.
- e) No additional payment shall be made for concrete testing as it is considered incidental to the Work of this specification.

#### 11. BACKFILLING AROUND CONCRETE FOUNDATIONS

- a) In addition to Specification 1002 M "Specifications for Supplying and Placing Granular Backfill", the following provisions will apply.
  - b) Placed concrete shall be allowed to cure for a minimum of 24-hours prior to backfilling and compaction of an approved granular material around the concrete pile foundation.
  - c) For traffic signal pole foundations, backfill shall be placed up to 50 mm from the concrete pile foundation surface. For controller foundations, backfill shall be placed up to 100 mm from the concrete pile foundation surface.
  - d) No additional payment shall be made for the supply or placement of backfill material as it shall be considered incidental to the Work of this Specification.
-

 <p><b>Manitoba</b> Infrastructure Traffic Engineering</p>	Specification No: 232
	<u>Effective Date</u> Current: November 2019
	Page 13 of 15
Specification For: Concrete Foundations for Traffic Signal and Pedestrian Corridor Structures	

## 12. QUALITY CONTROL

- a) All workmanship and all materials furnished and supplied under this Specification are subject to close and systematic inspection and testing by the Engineer, including all operations from the selection and production of materials, through to final acceptance of the Work. The Contractor shall be wholly responsible for the control of all operations incidental thereto notwithstanding any inspection or approval that may have been previously given. The Engineer reserves the right to reject any materials or Works that are not in accordance with the requirements of this Specification.
- b) The Contractor shall be responsible for making a thorough inspection of materials to be supplied under this Contract. All material shall be free of surface imperfections and other defects.

## 13. GUARANTEE

- a) The Contractor shall guarantee all material against quality or workmanship for a period of one (1) year after final approval by the purchaser.

## 14. METHOD OF MEASUREMENT

### 14.1 Construction of New Concrete Pile Foundations

The construction of cast-in-place concrete pile foundations will be measured on a unit basis for each type of foundation. The number of foundations to be paid for shall be the total number of foundations of each type, including all incidental materials, constructed in accordance with this Specification and accepted by the Engineer.

### 14.2 Construction of Concrete Pile Extensions

The construction of concrete pile extensions will be measured on a unit basis. The units to be paid for shall be the total number of pile extensions, including all incidental materials, constructed in accordance with this Specification and accepted by the Engineer.

### 14.3 Repair of Concrete Foundations

The repair of concrete foundations will be measured on a unit basis. The units to be paid for shall be the total number of foundations repaired, including all incidental materials, in accordance with this Specification and accepted by the Engineer.

### 14.4 Construction of Controller Base foundations

The construction of controller base foundations will be measured on a unit basis. The units to be paid for shall be the total number of foundations constructed, including all incidental materials, in accordance with this Specification and accepted by the Engineer.

---

## 15. BASIS OF PAYMENT

### 15.1 Construction of New Concrete Pile Foundations

The construction of cast-in-place concrete pile foundations will be paid for at the Contract Unit Price per unit for the "Items of Work" listed here below, measured as specified herein, which price shall be payment in full for supplying all materials and performing all operations described herein and all other items incidental to the Work included in this Specification.

Items of Work:

Construction of New Cast-in-Place Concrete Pile Foundations

Drawing No.	Description	Part No.
F1	Light Series Foundation: a) 610 mm Dia. Pile b) 610 mm Dia. Pile for Breakaway Base	F-L F-L(BR)
F2	Medium Series Foundation – 762 mm Dia. Pile	F-M
F3	Heavy Series Foundation – 915 mm Dia. Pile	F-H
F4	Extra Heavy Series Foundation – 1220 mm Dia. Pile	F-EH
A1	Anchor Bolts: a) 32 mm (1 1/4") Dia. Anchor Bolt b) 38 mm (1 1/2") Dia. Anchor Bolt c) 51 mm (2") Dia. Anchor Bolt	AB1 AB2 AB3

### 15.2 Construction of Concrete Pile Extensions

The construction of concrete pile extensions will be paid for at the Contract Unit Price per unit for "Construction of Concrete Pile Extensions," measured as specified herein, which price shall be payment in full for supplying all materials and performing all operations described herein and all other items incidental to the Work included in this Specification.

### 15.3 Repair of Concrete Foundations

The repair of concrete foundations will be paid for at the Contract Unit Price per unit for "Repair of Concrete Foundations," measured as specified herein, which price shall be payment in full for supplying all materials and performing all operations described herein and all other items incidental to the Work included in this Specification.

**Manitoba**



Infrastructure  
Traffic Engineering

Specification No: 232

Effective Date

Current: November 2019

Page 15 of 15

Specification For: Concrete Foundations for Traffic Signal and Pedestrian Corridor Structures

#### 15.4 Construction of Controller Base foundations

The construction of cast-in-place controller base foundations will be paid for at the Contract Unit Price per unit for "Construction of Controller Base Foundations," measured as specified herein, which price shall be payment in full for supplying all materials and performing all operations described herein and all other items incidental to the Work included in this Specification.

"Original Signed By"

Approved: \_\_\_\_\_

Glenn Cuthbertson, P. Eng.  
Director, Traffic Engineering Branch