




BILL OF PILES			Site No.	
LOCATION	DESCRIPTION	No. OF PILES	LENGTH	TOTAL LENGTH (m)
SU.1 & SU.5	Steel piles - HP310 x 110 (abutments)	12		0
SU.1 & SU.5	Steel piles - HP250 x 85 (wing walls)	8		0
TOTAL LENGTH OF PILES (m) =				
SU.2 - SU.4	Steel piles - HP310 x 110 (Intermediate bent)	27		0
TOTAL LENGTH OF PILES (m) =				
0				



BILL OF PILE TIPS		
LOCATION	DESCRIPTION	No. OF PILES
SU.1 & SU.5	Hard-Bite Point HP-77750-B for HP310 x 110 (Abutments)	12
SU.2 - SU.4	Hard-Bite Point HP-77750-B for HP310 x 110 (Intermediate bent)	27



- NOTES:**
re: Welding
- Low hydrogen +E70 series electrodes shall be used.
 - The minimum root pass shall be 6 mm.
 - Preparation for welding requires 13 mm bevel for HP 250 piles and 14 mm bevel for HP 310 piles.
 - Weld both flanges and web as shown. The inside beveling and welds to be completed first.
 - Before undertaking the back welds, the weld preparation shall be carried out with a carbon Arc-Air gouger.
- +E4801B equivalent metric electrode



- NOTES :**
- Edges of HP Steel pile tip to be ground on 45° bevel for 10 mm.
 - Low hydrogen +E70 series electrodes shall be used.
 - The minimum root pass shall be 6 mm.
- +E4801B equivalent metric electrode




- NOTES :**
re: Backfill Behind Abutment Ballast Walls
- Backfill behind ballast wall and wingwall panels shall be Type 1 - Granular backfill supplied and placed in accordance with Bridge Specification 1001 (I). The granular backfill shall be placed and compacted in lifts not exceeding 150 mm.
 - Compaction equipment used within 2 m of ballast walls and wingwalls shall be limited to light vibratory equipment with a mass not exceeding 120 kg unless otherwise approved.
 - Steel pile tip to be PRUYN "Hard-Bite" or equivalent.


REVISIONS		GENERAL ELEVATION	
DATE	BY	DESCRIPTION	RELEASED FOR CONSTRUCTION BY:
			EXECUTIVE DIRECTOR OF STRUCTURES DATE
DESIGN SEAL	RECORD SEAL		SCALE: 1:125 SHEET No. 2
PLACE ENGINEERS ELECTRONIC SEAL HERE		DESIGN BY: B.A.N.	or as shown SITE No. _____
		CHECKED: _____	
DETAILS		BY: K.P.	
		CHECKED: _____	

NORTH or WEST


SOUTH or EAST



PLAN



EDGE TREATMENT




OVERLAPPING DETAILS

RIP RAP DETAILS

Not To Scale

- NOTES:
1. All geotextile shall be Non-Woven Geotextile, Class I (Heavy Duty) from the Manitoba Infrastructure's Approved Product List.
 2. Geotextile shall be placed under all rip rap, overlapping 600mm in direction of flow.

NOTE:
Existing pile bents to be removed by Bridge Contractor.




ELEVATION
Scale 1:150

UTILITY DISCLAIMER:
LOCATIONS OF UTILITIES AS SHOWN ARE BASED ON READILY AVAILABLE INFORMATION. NO GUARANTEE IS GIVEN THAT ALL UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONTRACTOR SHALL CONFIRM THE EXISTENCE AND LOCATION OF UTILITIES BY OBTAINING FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.




REVISIONS		SITE AND EROSION CONTROL DETAILS	
DATE	BY	DESCRIPTION	RELEASED FOR CONSTRUCTION BY:
			EXECUTIVE DIRECTOR OF STRUCTURES DATE
			SCALE: 1:200 SHEET No. 4
			or as shown SITE No.

DESIGN BY: [Signature] CHECKED: [Signature]	DETAILS BY: K.P. CHECKED: [Signature]	Manitoba Infrastructure Water Management and Structures
		PLACE ENGINEERS ELECTRONIC SEAL HERE






PART SIDE ELEVATION

Bridge railing not shown for clarity



NOTES:

- RE-BOLTING
 - GIRDER LATERAL CONNECTION
 - Bolts Mk. "R1" - c/w one F436 hardened washer, one structural plate washer Mk. "W1", one pair Nord-Lock washers and one Grade DH heavy hex. nut.
 - STEEL CAP
 - Bolts Mk. "R30" - One F436 hardened washer, one hardened bevel washer and one Grade DH heavy hex. nut.
 - Bolts Mk. "R32" - One hardened bevel washer and one Grade DH heavy hex. nut.
 - Bolts Mk. "R35" - Two F436 hardened washers and one Grade DH heavy hex. nut.
 - PRECAST PANELS
 - Bolts Mk. "R36" - Two F436 hardened washers and one Grade DH heavy hex. nut.
 - Bolts Mk. "R34" - One F436 hardened washer and one structural plate washer Mk. "A2", no nuts.
 - Threaded rod Mk. "TR2" - One standard flat washer, one structural lock washer, structural plate washer Mk. "A1" and one stainless steel hex. nut.
 - Threaded rod Mk. "TR3" - two Filler plates Mk. "S4", one structural lock washer, two standard flat washers and two hex. nuts, Filler plate Mk. "S5" if required.
 - GIRDER TO STEEL CAP
 - Threaded rod Mk. "TR1" - one standard flat washer and structural lock washer and two hex. nuts.
 - High strength bolts shall be tightened by the turn-of-nut method as per Bridge Specifications. Ensure nuts are lubricated prior to bolting.
 - Fill counter bored holes with mastic filler after tightening bolts.
- When grouting dowel holes in girders, ensure that there is no grout between bottom of girder and bearing plate.
- Apply galvalloy to all field welds & areas where galvanizing has been damaged.
- Impregnated expanding joint sealant shall be installed as per manufacturer's recommendations.



NOTE:

For location of SECTIONS "B-B" & "DETAIL B" see Sheet No. 6.


REVISIONS		ASSEMBLY DETAILS	
DATE	DESCRIPTION		
		 Infrastructure Water Management and Structures	
		EXECUTIVE DIRECTOR OF STRUCTURES DATE	
		SCALE: 1:30 SHEET No. 7	
		or as shown SITE No.	

PLACE ENGINEERS ELECTRONIC SEAL HERE


BILL OF MISCELLANEOUS METAL 10 800 ROADWAY WIDTH - 4 SPAN								Site No.	
MARK No.	No.	DESCRIPTION	CORROSION PROTECTION	SIZE	LENGTH	REMARKS	COMPONENT MASS	MASS PER UNIT	TOTAL MASS
P1	2	Steel plate	Hot dip galvanized						1768.66
	Each unit to be fabricated from:								
	1	Steel plate		PL 32x550	6 400	See detail for Abutment	884.224	884.224	
	9	Nelson Type NBL, no thread studs		10 dia.	19	Part No. 101-063-167	0.012	0.108	
								884.332	
P1a	2	Steel plate	Hot dip galvanized						1768.66
	Each unit to be fabricated from:								
	1	Steel plate		PL 32x550	6 400	See detail for Abutment	884.224	884.224	
	9	Nelson Type NBL, no thread studs		10 dia.	19	Part No. 101-063-167	0.012	0.108	
								884.332	
P2	6	Steel plate	Hot dip galvanized						4522.90
	Each unit to be fabricated from:								
	1	Steel plate		PL 32x500	6 000	See detail for Intermediate Bent	753.600	753.600	
	18	Nelson Type NBL, no thread studs		10 dia.	19	Part No. 101-063-167	0.012	0.216	
								753.816	
P3	4	Steel channel	Hot dip galvanized	C310x45	12 800	See detail for Abutment	572.160	2288.64	
P4	6	Steel channel	Hot dip galvanized	C310x45	12 000	See detail for Intermediate Bent	536.400	3218.40	
R30	180	A325 bolt assembly	Hot dip galvanized	16 dia.	89	Steel plate to channels	0.245	44.10	
R32	48	A325 bolt assembly	Hot dip galvanized	16 dia.	76	Steel plate to channels Cbores holes	0.225	10.80	
R35	468	A325 bolt assembly	Hot dip galvanized	22 dia.	64	Channels to piles	0.461	215.75	
R36	48	A325 bolt assembly	Hot dip galvanized	16 dia.	64	Angles Mk. "S1" to piles & bracket Mk. "S2" to cap	0.205	9.84	
S1	20	Angle	Hot dip galvanized	L 152x152x13	250	As detailed	7.250	145.00	
S2	4	Bracket	Hot dip galvanized			As detailed	11.226	44.90	
S3	16	Plate	Hot dip galvanized	PL 6x300		As detailed	3.223	51.57	
S4	32	Filler plate	Hot dip galvanized	PL 6x100	300	As detailed	1.413	45.22	
S5	16	Filler plate	Hot dip galvanized	PL 3x100	300	As detailed	0.707	11.31	
A1	16	Structural plate w/asher	Hot dip galvanized	PL 10x150	150	As detailed - One to threaded rod Mk. "TR2"	1.766	28.26	
A2	8	Structural plate w/asher	Hot dip galvanized	PL 10x90	90	As detailed - One to bolt Mk. "R34"	0.636	5.09	
TR1	72	Threaded rods c/w tw o hex. nuts	Hot dip galvanized	19 dia.	400	Girder to steel cap plate	0.940	67.68	
TR3	32	Threaded rods c/w tw o hex. nuts	Hot dip galvanized	19 dia.	300	Steel plates Mk. "S3" to precast panels	0.660	21.12	
	228	Hardened bevel w/asher	Hot dip galvanized	for 16 dia. bolts		One to bolts Mk. "R30" & "R32"	0.110	25.08	
	16	Standard flat w/asher	Hot dip galvanized	for 13 dia. rod		One to threaded rod Mk. "TR2"	0.010	0.16	
	136	Standard flat w/asher	Hot dip galvanized	for 19 dia. rod		One to "TR1", two to "TR3"	0.020	2.72	
	16	Structural lock w/asher	Hot dip galvanized	for 12 dia. rod		One to threaded rod Mk. "TR2"	0.010	0.16	
	104	Structural lock w/asher	Hot dip galvanized	for 19 dia. rod		One to "TR1" & "TR3"	0.020	2.08	
	468	F436 Hardened w/asher	Hot dip galvanized	for 22 dia. bolts		One to bolt Mk. "R35"	0.032	14.98	
	48	F436 Hardened w/asher	Hot dip galvanized	for 16 dia. bolts		One to bolt Mk. "R36"	0.014	0.67	
R1	256	A325 bolt assembly	Hot dip galvanized	22 dia.	76	R.C. girder connection	0.499	127.74	
W1	256	Structural flat w/asher	Hot dip galvanized	for 22 dia. bolts		One to bolt Mk. "R1"	0.050	12.80	
	256	Pair Nord-Lock lock w/ashers		for 22 dia. bolts		One pair to bolt Mk. "R1"	0.020	5.12	
SH1	128	Shim plate	Hot dip galvanized	PL 2.5x80	180	As detailed - use as required	0.231	29.57	
SH2	128	Shim plate	Hot dip galvanized	PL 5x80	180	As detailed - use as required	0.463	59.26	
TOTAL MASS (kg) = 14548.24									

NOTES:



- All material noted in the above Bill shall be hot dip galvanized after fabrication in accordance with CSA G164 for a minimum net retention of 610 g/m² unless otherwise stated in the specified material ASTM standards. The fabricator and galvanizer shall safeguard against embrittlement using recommended practices from applicable standards.
- Seal all welds prior to galvanizing.
- Apply Galvaloy to all field welds and areas where galvanizing has been damaged.
- All bolts and threaded rod in the above Bill shall be Imperial thread.




ANGLE MK. "S1"




BRACKET MK. "S2"



FILLER PLATES MK. "S4" & "S5"



WASHER MK. "A1"



WASHER MK. "A2"





PLATE MK. "S3"



SHIM PLATES MK. "SH1" & "SH2"

REVISIONS		STEEL PILE CAP DETAILS	
DATE	DESCRIPTION		
		Manitoba Infrastructure Water Management and Structures	
		RELEASED FOR CONSTRUCTION BY: _____	
		EXECUTIVE DIRECTOR OF STRUCTURES DATE _____	
		DESIGN BY: _____ B.A.N.	SCALE: 1:5
		CHECKED: _____	SHEET No. 9
		DETAILS BY: _____ K.P.	SITE No. _____
		CHECKED: _____	or as shown

PLACE ENGINEERS
ELECTRONIC SEAL
HERE





NORTH OR WEST

SOUTH OR EAST

BILL OF BEARINGS 10 800 ROADWAY WIDTH - 4 SPAN Site No.

No.	LOCATION	DESCRIPTION	REMARKS
72	SU.1 - SU.5	Elastomeric bearings	As detailed


NOTE:
 1. Elastomer shall be natural rubber. Elastomer shall be AASHTO low temperature Grade 5 with a minimum shear modulus $G \geq 0.9$ MPa and a 60 durometer Shore A hardness.
 2. Internal steel reinforcing plates for laminate bearings shall be rolled mild steel with a minimum yield strength of 300 Mpa.




NOTES:

- Re: Girder Erection Operations Behind Abutment Ballast Walls*
- Surcharge loading on the backfill resulting from girder erection operations shall be minimized near the precast concrete ballast walls and wingwalls.
 - Where possible, girder erection equipment shall be positioned such that there are no surcharge loads behind the back face of the precast panels within a distance equal to the depth of backfill to the bottom of the panels at the time of girder erection.
 - Should the Contractor propose to encroach on this zone, the following requirements must be satisfied:
 - Submit a girder erection procedure for approval outlining type, configuration, weights and locations of equipment including expected tipping forces on crane outriggers, etc.
 - Perform all precautionary measures outlined by the Department as a result of that submission.
 - All surcharge loads encroaching in this zone must be distributed over an area not less than 2.0 m².


REVISIONS		BEARING AND ERECTION DETAILS	
DATE	DESCRIPTION		
		Manitoba Infrastructure Water Management and Structures	
		RELEASED FOR CONSTRUCTION BY: _____ DATE: _____ EXECUTIVE DIRECTOR OF STRUCTURES	
		SCALE: 1:125 SHEET No. 10	
PLACE ENGINEERS ELECTRONIC SEAL HERE		or as shown SITE No. _____	




ELEVATION
GIRDER STRAND LAYOUT



END VIEW
Typical layout of 20 - 13 #
Low Relaxation straight strands



PART PLAN
Typical at both ends of girders





SECTION E-E
Scale 1:5

BEARING RECESS DETAILS

REVISIONS		PRECAST PRESTRESSED CHANNEL GIRDER DETAILS		
DATE	BY	DESCRIPTION		
		DESIGN SEAL	RECORD SEAL	
				RELEASED FOR CONSTRUCTION BY:
				EXECUTIVE DIRECTOR OF STRUCTURES DATE
				SCALE: Scale 1:20 SHEET No. G2
		DESIGN BY: B.A.N.		
		CHECKED: _____		
		DETAILS BY: K.P.		
		CHECKED: _____		
			or as shown SITE No. 0000	

PLACE ENGINEERS
ELECTRONIC SEAL
HERE



BILL OF REINFORCING FOR PRECAST PANELS


SITE _____

MARK	TYPE	PIN DIAMETER	LENGTH	PANEL TYPE	No. of PANELS	No. of BARS PER PANEL	TOTAL No. of BARS PER PANEL TYPE	BENDING DIAGRAM
1501_N1	STR		6 300	N1	2	6	12	
1502_N1	STR		600	N1	2	22	44	
1501_N1a	STR		6 300	N1a	2	6	12	
1502_N1a	STR		600	N1a	2	22	44	
1501_N2	STR		7 450	N2	2	10	20	
1502_N2	STR		1 200	N2	2	26	52	
1501_N3	STR		5 150	N3	2	10	20	
1502_N3	STR		1 200	N3	2	18	36	
1501_N4	STR		4 900	N4	2	16	32	
1502_N4	STR		1 900	N4	2	17	34	
1501_N4a	STR		4 900	N4a	2	16	32	
1502_N4a	STR		1 900	N4a	2	17	34	

Total mass of reinforcing steel							1576.91	kg
Panel Type	N1	N1a	N2	N3	N4	N4a		
Area m ² /panel	4.50	4.50	9.80	6.80	10.00	10.00		
Total area of precast Panels							91.20	m ²

NOTES:

- All dimensions given in bending diagram are out to out, except radii and extensions on 90°, 135° & 180° hooks. Extensions on 90°, 135° & 180° hooks are the "A" of "C" dimensions for standard 90°, 135° & 180° hooks referenced from the RSIC "Manual of Standard Practice". Radii are inside dimensions. All reinforcing steel bends and hooks shall conform to Clause 6.6.2 of C.S.A. A23.1-04, unless noted otherwise in the BILL OF REINFORCING STEEL.
- All reinforcing steel shall be deformed steel, unless noted otherwise in the BILL OF REINFORCING STEEL.
- All reinforcing steel shall conform to CSA G30.18-M92 "Billet Steel Bars for Concrete Reinforcement" Grade 400W, unless noted otherwise in the BILL OF REINFORCING STEEL.
- Like bars shall be bundled, securely tied and identified as to Mark and Site No. by appropriate means. All other items to be identified in a similar fashion.
- All bars shall be bent in accordance with the following detail:





BILL OF MISCELLANEOUS METAL for PRECAST PANELS

Site No. _____

MARK No.	No.	DESCRIPTION	CORROSION PROTECTION	SIZE	LENGTH	REMARKS
Q5	4	Insert units	Hot dip galvanized			
		Each unit is fabricated from:				
		Steel plate		PL 10 x 150	250	As detailed
		2 - Studs Mk. "A1"		13 dia.	75	Nelson headed concrete anchors, Type H4L, Part No. 101-053-002 - As detailed
		3 - Bars Mk. "A2"		10 dia.	300	Nelson deformed bar anchors, Type D2L, Part No. 101-064-537 - As detailed
		2 - Heavy hex. nuts		for 19 dia. bolt		Grade DH or 2H heavy hex. nut, c/w metal or plastic sleeve
R34	8	A325 bolt c/w F436 hardened w washer		19 dia.	60	

NOTES:

- All material noted in the above Bill shall be hot dip galvanized after fabrication in accordance with CSA G164 for a minimum net retention of 610 g/m² unless otherwise stated in the specified material ASTM standards. The fabricator and galvanizer shall safeguard against embrittlement using recommended practices from applicable standards.
- Seal all welds prior to galvanizing.
- All structural steel to be CSA G40.21 Grade 300W.
- All bolts and inserts in the above Bill shall be Imperial thread.



NOTES:

- For location of DETAIL "A" see sheet No. P1.
- Precast panel concrete strength: f_c = 35 MPa.

REVISIONS		PRECAST PANEL DETAILS			
20__/__/____	ISSUED FOR CONSTRUCTION				
DATE	BY	DESCRIPTION	RELEASED FOR CONSTRUCTION BY:		
DESIGN SEAL	RECORD SEAL				
PLACE ENGINEERS ELECTRONIC SEAL HERE		<p>Infrastructure Water Management and Structures</p>			
				EXECUTIVE DIRECTOR OF STRUCTURES DATE	
				SCALE: 1:2 SHEET No. P2	
				OR as shown SITE No. _____	